

Concession Area/Café Checklist



CONC1	Agency Name:		
CONC2	Total number of concession areas/cafés assessed:	_____ concession areas	
CONC3	Name/ location of the concession area/caf�:		
CONC4	Is there a continuous unobstructed route of travel from entrance (if indoor facility) or parking (if outdoor facility) to the concession area/caf�?	<input type="checkbox"/> yes <input type="checkbox"/> no <input type="checkbox"/> n/a <input type="checkbox"/> photo	
CONC5	Is the route of travel well-lit?	<input type="checkbox"/> yes <input type="checkbox"/> no <input type="checkbox"/> n/a <input type="checkbox"/> photo	
CONC6	Describe the surface of the route of travel:		
CONC7	Slope of route of travel (at its steepest incline):	_____ % (enter 0% if flat)	
CONC8	Width of route of travel (at its narrowest point):	_____ inches (at least 36")	
CONC9	Location of concession area/caf�:	<input type="checkbox"/> indoors <input type="checkbox"/> outdoors	
CONC10	Is there an entrance to the concession area/caf�?	<input type="checkbox"/> yes <input type="checkbox"/> no <input type="checkbox"/> n/a <input type="checkbox"/> photo	
CONC11	If yes, clear open width of door or entrance to concession area/caf�:	_____ inches (at least 32")	
CONC12	Opening force of door:	_____ pounds (5 pounds or less)	
CONC13	Handle type entering : <input type="checkbox"/> automatic <input type="checkbox"/> knob <input type="checkbox"/> pull <input type="checkbox"/> push/pull paddle/bar <input type="checkbox"/> entry set-top button <input type="checkbox"/> lever <input type="checkbox"/> push plate <input type="checkbox"/> other:		
CONC14	Handle type exiting : <input type="checkbox"/> automatic <input type="checkbox"/> knob <input type="checkbox"/> pull <input type="checkbox"/> push/pull paddle/bar <input type="checkbox"/> entry set-top button <input type="checkbox"/> lever <input type="checkbox"/> push plate <input type="checkbox"/> other:		
CONC15	Clear space on pull side of door:	_____ inches (at least 18")	
CONC16	If applicable, what is the height of the caf�/concession counter?	_____ inches (36" maximum)	
CONC17	If applicable, does the food service line provide clear space that is least 36" wide? (preferred clear width of 42")	<input type="checkbox"/> yes <input type="checkbox"/> no <input type="checkbox"/> n/a <input type="checkbox"/> photo	
CONC18	If applicable, what is the height of tableware, dishware, condiment, food and beverage display shelves, and dispensing devices:	_____ inches (36" maximum)	
CONC19	Does this concession area/caf� provide seating?	<input type="checkbox"/> yes <input type="checkbox"/> no <input type="checkbox"/> n/a <input type="checkbox"/> photo	
CONC20	If yes, are there tables that offer wheelchair seating? (60" of clear floor space & tables that are 28 -34" high?)	<input type="checkbox"/> yes <input type="checkbox"/> no <input type="checkbox"/> n/a <input type="checkbox"/> photo	
CONC21	If yes, how many tables that accommodate wheelchair users are available?	_____ tables (5% minimum)	
CONC22	If yes, is there a minimum of 36" of access route between/around tables?	<input type="checkbox"/> yes <input type="checkbox"/> no <input type="checkbox"/> n/a <input type="checkbox"/> photo	
CONC23	If yes, are there wheelchair seating tables which have a 36" access route from the tables to the restroom?	<input type="checkbox"/> yes <input type="checkbox"/> no <input type="checkbox"/> n/a <input type="checkbox"/> photo	
CONC24	Are menus offered in alternative formats?	<input type="checkbox"/> yes <input type="checkbox"/> no <input type="checkbox"/> n/a <input type="checkbox"/> photo	
CONC25	If yes check the alternative forms of communication available: <input type="checkbox"/> assisted listening devices <input type="checkbox"/> large print <input type="checkbox"/> oral communication provided in print <input type="checkbox"/> sign language <input type="checkbox"/> Braille <input type="checkbox"/> multiple languages <input type="checkbox"/> pictorial <input type="checkbox"/> other:		
CONC26	Comments/additional information about concession area or caf�:		

Concession Area/Café Checklist Information

Additional information for completing the Concession Area/Café checklist:


Menus – For individuals who are blind or have low vision, restaurants should offer menus in an alternative format, such as Braille or large print. If this is not feasible, restaurants should train staff on how to assist customers who are blind or have low vision.

At least 5% of all fixed seating or tables provided shall be accessible by a route at least 36" wide from the entrance and also have an access route to the restroom facilities. Where it is practical, accessible tables should be distributed throughout the space or facility.

If seating spaces for people who use wheelchairs are provided at tables or counters, 60" of clear floor space shall be provided.

The tops of tables should be between 28" and 34" high from the floor or ground.

Food service lines shall have a minimum clear width of 36", with a preferred clear width of 42" where passage of stopped wheelchairs by pedestrians is desired. Tray slides shall be mounted no higher than 34" above the floor.



Food Service Lines